



बर्दिबास नगरपालिका
नगरकार्यपालिकाको कार्यालय

टेलिफोन नं ०४४-५५००९०
इमेल: bardibashospital@gmail.com

बर्दिबास अस्पताल

पत्र संख्या: २०८२/०८३
चलानी नं.

महोत्तरी, मेची प्रदेश, नेपाल
स्थापना: २०६५

मिति: २०८२/०७/२९

विषय: प्रस्ताव पेश गर्ने सम्बन्धमा ।

श्री ईजाजत प्राप्त फर्म/कम्पनी/निर्माण व्यवसायी सबै,

प्रस्तुत विषयमा चालु आ.व. २०८२/८३ को लागि बर्दिबास अस्पतालको स्वीकृत वार्षिक कार्यक्रम अन्तर्गत विनियोजित रकमबाट वाल पार्टेशन तथा ट्रेस निर्माण कार्य गर्नु पर्ने भएकाले बर्दिबास अस्पतालबाट स्वीकृत लागत अनुमान रु.९,५८,११४।५३ (अक्षरेपी नौ लाख अन्ठाउन्न हजार हजार एक सय चौध रुपैया त्रिपन्न पैसा मात्र, मू.अ.कर समेत) को परिधि भित्र रही यसै साथ संलग्न B0Q फाराम भरि तथा तपसिलमा उल्लेखित कागजातहरु समेत संलग्न राखि यो सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र दररेट सहितको सिलबन्दी प्रस्ताव पेश गर्नु हुन अनुरोध छ ।

तपसिल:

- फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी
- VAT तथा PAN प्रमाण पत्रको प्रतिलिपी
- आ.व. २०८१/८२ को करचुक्ता/म्याद थप प्रमाण पत्रको प्रतिलिपी


दिपेश कुमार काफ्ले
अधिकृत सातौं प्रशासक
अस्पताल प्रशासन शाखा प्रमुख



BARDIBAS HOSPITAL

Bardibas Municipality

Bardibas, Mahottari

Madhes, Pradesh, Nepal

Bill of Quantity (BOQ)

धरमपुर नगरपालिका
वडा नं. १
२०६३

Name of the Project :- बर्दिबास अस्पतालमा बाल पार्किंग तथा ट्रस्ट निर्माण

Location :- बर्दिबास नगरपालिका, वडा नं. :- २

Fiscal Year :- २०६३/०६३

S. No.	Description of works	Unit	Quantity	Rate (NRS)		Amount (NRS)	Remarks
				In Figures	In Words		
A	Partition Works						
1	Supplying and Fixing of Aluminium partition with 5mm thick glass and 9mm thick laminated board of section (101x45x1.1)	Sqm.	45.77				
B	Truss Works						
2	Earth work excavation in foundation in clay & soft murrain stone (upto 30 cm.) mix with hard soil lead upto 10 m. & upto lift 1.5 m.	Cum.	5.99				
3	Stone Soiling Works	Cum.	7.08				
4	P.C.C. (1:3:6) works in foundation	Cum.	0.86				

1
दिपेश कुमार कापले
अधिकृत सातौं (प्रशासन)
अस्पताल प्रशासन शाखा प्रमुख



विशेष कुमार कापले
अधिकृत सहाय प्रशासक
अस्पताल प्रशासन शाखा मुंबई

5	P.C.C. (1:2:4) works in foundation	Cum.	7.67				
6	Tor steel reinforcement bar for R.C.C. work with cutting, bending, binding & laying with all complete.	kg	98.84				
7	Store masonry in 1:6 cement sand mortar	Cum.	5.13				
8	3 mm thick Cement sand 1:1 flushing plaster.	Sqm.	71.54				
9	MS Truss Works	kg	631.16				
10	3mm Carbon fiber UPVC roofing sheet including cost of materials and labour fitting all complete.	Sqm.	77.42				
	Total Amount						
	VAT @ 13%						
	Total Amount including VAT						

Name of Contractor :-

Address of Contractor:-

Signature and Stamp:-

Date:-