



बर्दिबास नगरपालिका
नगरकार्यपालिकाको कार्यालय

टेलिफोन नं ०४४-५५००९०
इमेल: bardibashospital@gmail.com

बर्दिबास अस्पताल

पत्र संख्या: २०८२/०८३
चलानी नं.

महोत्तरी, पश्चिमाञ्चल प्रदेश, नेपाल
स्थापित: २०६३

मिति: २०८२/०७/२९

विषय: प्रस्ताव पेश गर्ने सम्बन्धमा।

श्री ईजाजत प्राप्त फर्म/कम्पनी/निर्माण व्यवसायी सबै,

प्रस्तुत विषयमा चालु आ.व. २०८२/८३ को लागि बर्दिबास अस्पतालको स्वीकृत वार्षिक कार्यक्रम अन्तर्गत विनियोजित रकमबाट शौचालय मर्मत सम्भार गर्नु पर्ने भएकाले बर्दिबास अस्पतालबाट स्वीकृत लागत अनुमान रु.८,८२,८०८।३९ (अक्षरेपी आठ लाख बयासी हजार आठ सय आठ रुपैया उनन्चालीस पैसा मात्र, मू.अ.कर समेत) को परिधि भित्र रही यसै साथ संलग्न B0Q फाराम भरि तथा तपसिलमा उल्लेखित कागजातहरु समेत संलग्न राखि यो सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र दररेट सहितको सिलबन्दी प्रस्ताव पेश गर्नु हुन अनुरोध छ।

तपसिल:

- फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी
- VAT तथा PAN प्रमाण पत्रको प्रतिलिपी
- आ.व. २०८१/८२ को करचुक्ता/म्याद थप प्रमाण पत्रको प्रतिलिपी


दिनेश कुमार काफ्ले
अधिकृत सार्वजनिक प्रशासना
अस्पताल प्रशासन शाखा प्रमुख



BARDIBAS HOSPITAL

Bardibas Municipality

Bardibas, Mahottari

Madhesh Pradesh, Nepal

Bill of Quantity (BOQ)

Signature

दिपेश कुमार कापले

3
2075

Name of the Project :- बर्दिबास अस्पतालमा टोइलेट मर्मत

Location:- बर्दिबास नगरपालिका, वडा नं. :-२

Fiscal Year:- २०८२/०८३

S. No.	Description of works	Unit	Quantity	Rate (NRs)		Amount (NRs)	Remarks
				In Figures	In Words		
A	Aluminium Partation Work						
1	Supplying and Fixing of Aluminium partition with 5mm thick glass and 9mm thick laminated board of section (101x45x1.1)	sqm	15.50				
B	Maintainence Work of all Toilet						
2	Dismantling work of P.C.C. / L.C.C. & removing of material upto 10 m. lead.	cum	6.80				
3	P.C.C. (1:3:6) work in foundation, wall (River bed).	cum	5.98				
4	Porcelain non-glazed tile paving work in cement sand (1:4) mortar.	sqm	54.18				



दिपेक्ष कर्मकार कर्मचारी
आधिकारिक पत्राचार
अरुणोत्तम प्रजापति शाखा प्रमुख

13	Sink Coupling	Pcs	15.00				
14	Tap Short Body	Pcs	4.00				
15	Tap Long Body	roll	10.00				
16	Connection Pipe 24"	Pcs	2.00				
17	Connection Pipe 36"	Pcs	2.00				
18	Connection Pipe 12"	Pcs	4.00				
19	Comode -9"	pcs	5.00				
20	Comode Spray	Pcs	15.00				
21	Urinal Partition white glazed porcelain Clay (68*30)cm	Pcs	6.00				
22	Wash Basin (medium)(22*16)cm	Pcs	1.00				
23	Angle Cock single	Pcs	4.00				
24	Angle Valve 2in1	Pcs	13.00				
25	Tape(Big)	roll	1.00				
26	Cpvc Tee 2"	Pcs	1.00				
27	Cpvc Socket 2"	Pcs	1.00				
28	Cpvc Pipe 20mm	rm	10.00				
29	Cpvc Elbow 20mm	Pcs	1.00				



Signature
दिपेश ठाकुर कापले
अधीक्षक
अधीक्षक

30	Cpvc Female Elbow.36mm	Pcs	1.00				
31	Siphone For Pan	Pcs	3.00				
32	Cpvc Jointing materials (flow guard adhesive sojn)	m.	3.00				
33	Pillar Cock 1/2"	Pcs	5.00				
34	Waste Pipe	Pcs	15.00				
35	Udisa Pan	Pcs	1.00				
36	CPVC Solvent (237MI)	Pcs	2.00				
37	Fittings installation work and miscellaneous works	Ls	1.00				
	Total Amount						
	VAT @ 13%						
	Total Amount including VAT						

Name of Contractor :-

Address of Contractor:-

Signature and Stamp:-

Date:-